Amendment-IV dated 26.10.2026 on the Request for Proposal document for Selection of Bidder as Transmission Service Provider to establish Inter-State Transmission system for "Transmission scheme for evacuation of power as part of Rajasthan REZ Ph-IV (Part-6: 6 GW) (Bikaner Complex) (Bikaner V: 6 GW)- Part A" through tariff based competitive bidding process.

Sl. No.	Clause No.	Existing Clause	New/Revised Clause
1.	Specific Technical Requirements for Substation of RfP and TSA documents Clause No. B.1.2	**B.1.2 Switching scheme** **….** ***Notes:-*** **….** *viii) 765/400/220 kV Pallu S/s:* *765 kV Bay configuration at Pallu S/s shall consist of 08 Nos. of full diameter (one diameter consist of two Nos. Main and associated Tie bays) for termination of ICT /Bus Reactor/Line bays/Line bays with Switchable Line reactor. Further, all associated interconnection work shall also be in the present scope of TSP.* *400 kV Bay configuration at Pallu S/s shall consist of 03 Nos. of full diameter (one diameter consist of two Nos. Main and associated Tie bays) for termination of ICT /Bus Reactor/Line bays/Line bays with Switchable Line reactor. Further, all associated interconnection work shall also be in the present scope of TSP.*	**B.1.2 Switching scheme** **….** ***Notes:-*** **….** *viii) 765/400/220 kV Pallu S/s:* *765 kV Bay configuration at Pallu S/s shall consist of 08 Nos. of full diameter (one diameter consist of two Nos. Main and associated Tie bays) for termination of ICT /Bus Reactor/Line bays/Line bays with Switchable Line reactor. Further, all associated interconnection work shall also be in the present scope of TSP.* *400 kV Bay configuration at Pallu S/s shall consist of 03 Nos. of full diameter (one diameter consist of two Nos. Main and associated Tie bays) for termination of ICT /Bus Reactor/Line bays/Line bays with Switchable Line reactor. Further, all associated interconnection work shall also be in the present scope of TSP.* ***At Pallu S/s, four (04) nos. of 765 kV line bays for termination of "765 kV Pallu-Panipat 2xD/c line" shall be constructed under the scheme "Transmission system for evacuation of power from Rajasthan REZ Ph-IV (Part-6 GW) [Bikaner-V]: Part-A". Whereas, four (04) nos. of 765 kV, 240 MVAr switchable line reactors associated with the above termination of "765 kV Pallu-Panipat 2xD/c line" shall be implemented under the scheme "Transmission system for evacuation of power from Rajasthan REZ Ph-IV (Part- 6 GW) [Bikaner-V]: Part-B".*** ***Hence, TSP shall provide suitable space at Pallu S/s for installation of the switchable line reactors envisaged under the scheme "Transmission System for Evacuation of Power from Rajasthan REZ Ph-IV (Part-6 GW) [Bikaner-V]: Part-B".***

<table>
<tr>
<td>2.</td>
<td>Scope of work and Clause 1.2 of the RFP document

Schedule: 1 of the TSA document</td>
<td>
<table>
<tr><th>Sl. No.</th><th>Scope of the Transmission Scheme</th><th>Scheduled COD in months from Effective Date</th></tr>
<tr><td>1.</td><td>Establishment of 765/400 kV, 6x1500 MVA & 400/220 kV, 10x500 MVA Bikaner-V Pooling Station along with 2x240 MVAr (765 kV) & 2x125 MVAr (420 kV) Bus Reactors at a suitable location near Bikaner

Bikaner-V PS – AIS
• 765/400 kV 1500 MVA ICTs- 6 Nos. (19x500 MVA including one spare unit)
• 400/220 kV 500 MVA ICTs- 10 Nos. <u>(for 765 kV interconnection with Pallu S/s)</u>
…….</td><td rowspan="7">36 months</td></tr>
<tr><td>2.</td><td>…</td></tr>
<tr><td>3.</td><td>…</td></tr>
<tr><td>4.</td><td>…</td></tr>
<tr><td>5.</td><td>…</td></tr>
<tr><td>6.</td><td>…</td></tr>
<tr><td>7.</td><td>……</td></tr>
</table>
</td>
<td>
<table>
<tr><th>Sl. No.</th><th>Scope of the Transmission Scheme</th><th>Scheduled COD in months from Effective Date</th></tr>
<tr><td>1.</td><td>Establishment of 765/400 kV, 6x1500 MVA & 400/220 kV, 10x500 MVA Bikaner-V Pooling Station along with 2x240 MVAr (765 kV) & 2x125 MVAr (420 kV) Bus Reactors at a suitable location near Bikaner

Bikaner-V PS – AIS
• 765/400 kV 1500 MVA ICTs- 6 Nos. (19x500 MVA including one spare unit)
• 400/220 kV 500 MVA ICTs- 10 Nos.
…….</td><td rowspan="7">36 months</td></tr>
<tr><td>2.</td><td>…</td></tr>
<tr><td>3.</td><td>…</td></tr>
<tr><td>4.</td><td>…</td></tr>
<tr><td>5.</td><td>…</td></tr>
<tr><td>6.</td><td>…</td></tr>
<tr><td>7.</td><td>……</td></tr>
</table>
</td>
</tr>
</table>

3.	Clause No. 3.3 of the SPA document	The Selected Bidder shall immediately upon receiving the Sale Share Certificates and the Share Transfer Forms, duly execute the Share Transfer Forms and duly lodge the Share Transfer Forms and the Share Certificates with the Company along with the names of its nominees to be appointed on the Board of the Company. **The new registered office address of the Company shall be within the jurisdiction of the RoC of New Delhi or within the jurisdiction of any other RoC, as required by selected bidder**, by following the due process as may be required, which would be the new registered office of the Company. The Company shall, upon receipt of the said documents from the Selected Bidder, do the following	The Selected Bidder shall immediately upon receiving the Sale Share Certificates and the Share Transfer Forms, duly execute the Share Transfer Forms and duly lodge the Share Transfer Forms and the Share Certificates with the Company along with the names of its nominees to be appointed on the Board of the Company. **The new registered office address of the Company shall be within the jurisdiction of the RoC, New Delhi-I**, by following the due process as may be required, which would be the new registered office of the Company. The Company shall, upon receipt of the said documents from the Selected Bidder, do the following:
4.	Clause No. 3.3 (i) (c) of the SPA document	changing the address of the registered office of the Company to the new address as provided by the Selected Bidder as per clause 3.3 above.	changing the address of the registered office of the Company to the new address **within 30 days as per statutory provisions** as provided by the Selected Bidder as per clause 3.3 above.