

Amendment – XIII dated 29.10.2020 on the Request for Proposal and Transmission Service Agreement issued for selection of bidder as Transmission Service Provider to establish “Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B” through tariff based competitive bidding process

Sl. No.	Clause No.	Existing Provisions	New / Revised Clause																										
1.	Point No. 2, Clause 1.2 of RFP & Schedule-2 of TSA	<p>.....</p> <table border="1"> <thead> <tr> <th data-bbox="327 391 436 529">S. No</th> <th colspan="2" data-bbox="443 391 1161 529">Transmission System for Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B</th> </tr> <tr> <th data-bbox="327 534 436 630"></th> <th data-bbox="443 534 926 630">Name of Transmission Element</th> <th data-bbox="932 534 1161 630">Scheduled COD in months from Effective Date</th> </tr> </thead> <tbody> <tr> <td data-bbox="327 634 436 708">1.</td> <td data-bbox="443 634 926 708">Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)</td> <td data-bbox="932 634 1161 1421" rowspan="3">18 Months</td> </tr> <tr> <td data-bbox="327 712 436 867">2.</td> <td data-bbox="443 712 926 867">2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)</td> </tr> <tr> <td data-bbox="327 872 436 1421">3.</td> <td data-bbox="443 872 926 1421"> 1x240 MVAR Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd) 240 MVAR, 765 kV reactor- 4 (2 reactors each at Fatehgarh-II and Bhadla-II). Switching equipment for 765 kV reactor - 4 (2 Switching equipments each at Fatehgarh-II and Bhadla-II) (1x80 MVAR Spare* reactor each at Fatehgarh-II and Bhadla-II to be </td> </tr> </tbody> </table>	S. No	Transmission System for Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B			Name of Transmission Element	Scheduled COD in months from Effective Date	1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 Months	2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)	3.	1x240 MVAR Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd) 240 MVAR, 765 kV reactor- 4 (2 reactors each at Fatehgarh-II and Bhadla-II). Switching equipment for 765 kV reactor - 4 (2 Switching equipments each at Fatehgarh-II and Bhadla-II) (1x80 MVAR Spare* reactor each at Fatehgarh-II and Bhadla-II to be	<p>.....</p> <table border="1"> <thead> <tr> <th data-bbox="1188 391 1297 529">S. No</th> <th colspan="2" data-bbox="1304 391 2024 529">Transmission System for Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B</th> </tr> <tr> <th data-bbox="1188 534 1297 630"></th> <th data-bbox="1304 534 1787 630">Name of Transmission Element</th> <th data-bbox="1793 534 2024 630">Scheduled COD in months from Effective Date</th> </tr> </thead> <tbody> <tr> <td data-bbox="1188 634 1297 708">1.</td> <td data-bbox="1304 634 1787 708">Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)</td> <td data-bbox="1793 634 2024 1421" rowspan="3">18 Months</td> </tr> <tr> <td data-bbox="1188 712 1297 867">2.</td> <td data-bbox="1304 712 1787 867">2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)</td> </tr> <tr> <td data-bbox="1188 872 1297 1421">3.</td> <td data-bbox="1304 872 1787 1421"> 1x240 MVAR Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd) 240 MVAR, 765 kV reactor- 4 (2 reactors each at Fatehgarh-II and Bhadla-II). Switching equipment for 765 kV reactor - 4 (2 Switching equipments each at Fatehgarh-II and Bhadla-II) (1x80 MVAR Spare* reactor each at Fatehgarh-II and Bhadla-II to be </td> </tr> </tbody> </table>	S. No	Transmission System for Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B			Name of Transmission Element	Scheduled COD in months from Effective Date	1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 Months	2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)	3.	1x240 MVAR Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd) 240 MVAR, 765 kV reactor- 4 (2 reactors each at Fatehgarh-II and Bhadla-II). Switching equipment for 765 kV reactor - 4 (2 Switching equipments each at Fatehgarh-II and Bhadla-II) (1x80 MVAR Spare* reactor each at Fatehgarh-II and Bhadla-II to be
S. No	Transmission System for Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B																												
	Name of Transmission Element	Scheduled COD in months from Effective Date																											
1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 Months																											
2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)																												
3.	1x240 MVAR Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd) 240 MVAR, 765 kV reactor- 4 (2 reactors each at Fatehgarh-II and Bhadla-II). Switching equipment for 765 kV reactor - 4 (2 Switching equipments each at Fatehgarh-II and Bhadla-II) (1x80 MVAR Spare* reactor each at Fatehgarh-II and Bhadla-II to be																												
S. No	Transmission System for Transmission system strengthening for evacuation of power from solar energy zones in Rajasthan (8.1 GW) under Phase II –Part B																												
	Name of Transmission Element	Scheduled COD in months from Effective Date																											
1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 Months																											
2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)																												
3.	1x240 MVAR Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd) 240 MVAR, 765 kV reactor- 4 (2 reactors each at Fatehgarh-II and Bhadla-II). Switching equipment for 765 kV reactor - 4 (2 Switching equipments each at Fatehgarh-II and Bhadla-II) (1x80 MVAR Spare* reactor each at Fatehgarh-II and Bhadla-II to be																												

Sl. No.	Clause No.	Existing Provisions					New / Revised Clause																								
			<p>used as spare for Fatehgarh-II – Bhadla-II 765kV D/c line (2nd))</p> <p>*not under the present scope</p>					<p>used as spare for Fatehgarh-II – Bhadla-II 765kV D/c line (2nd))</p> <p>*not under the present scope</p>																							
		<p>Note:</p> <p>i. POWERGRID to provide space for 2 no of 765 kV bays each at Fatehgarh-II and Bhadla-II substation and space for 2 no of switchable line reactors each at Fatehgarh-II and Bhadla-II substation</p> <p>ii. TSP shall install the 765kV Line Reactor banks at Bhadla II PS under each of the schemes (Part-B, Part-C and Part-E) and all the associated equipment required for switching arrangement viz isolators, circuit breakers, 765kV & 145kV (neutral) auxiliary buses etc., so that spare 1-ph unit, whenever provided in future, is able to replace any of the faulty unit without its physical movement. Respective TSP shall provide the equipment/facilities at Bhadla II PS such that only supply & installation of 1x80 MVAR spare unit of Reactor, associated LA, 1-Ph Circuit Breaker and extension of 765kV & 145kV buses will be required for completion of switching arrangement in future.</p>					<p>Note:</p> <p>i. POWERGRID to provide space for 2 no of 765 kV bays each at Fatehgarh-II and Bhadla-II substation and space for 2 no of switchable line reactors each at Fatehgarh-II and Bhadla-II substation</p> <p>ii. TSP shall install the 765kV Line Reactor banks at Bhadla II PS under each of the schemes (Part-B, Part-C and Part-E) and all the associated equipment required for switching arrangement viz isolators, circuit breakers, 765kV & 145kV (neutral) auxiliary buses etc., so that spare 1-ph unit, whenever provided in future, is able to replace any of the faulty unit without its physical movement. Respective TSP shall provide the equipment/facilities at Bhadla II PS such that only supply & installation of 1x80 MVAR spare unit of Reactor, associated LA, 1-Ph Circuit Breaker and extension of 765kV & 145kV buses will be required for completion of switching arrangement in future.</p>																								
2.	Clause 2.6.1 of RFP & Schedule -3 of TSA	<table border="1"> <thead> <tr> <th data-bbox="321 1036 420 1382">Sr. No</th> <th data-bbox="420 1036 604 1382">Name of the Transmission Element</th> <th data-bbox="604 1036 751 1382">Schedule d COD in months from Effective Date</th> <th data-bbox="751 1036 961 1382">Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project</th> <th data-bbox="961 1036 1161 1382">Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element</th> </tr> </thead> <tbody> <tr> <td colspan="5" data-bbox="321 1036 1161 1382">.....</td> </tr> </tbody> </table>					Sr. No	Name of the Transmission Element	Schedule d COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element					<table border="1"> <thead> <tr> <th data-bbox="1182 1036 1281 1382">Sr. No</th> <th data-bbox="1281 1036 1465 1382">Name of the Transmission Element</th> <th data-bbox="1465 1036 1612 1382">Schedule d COD in months from Effective Date</th> <th data-bbox="1612 1036 1822 1382">Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project</th> <th data-bbox="1822 1036 2022 1382">Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element</th> </tr> </thead> <tbody> <tr> <td colspan="5" data-bbox="1182 1036 2022 1382">.....</td> </tr> </tbody> </table>					Sr. No	Name of the Transmission Element	Schedule d COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element				
Sr. No	Name of the Transmission Element	Schedule d COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element																											
.....																															
Sr. No	Name of the Transmission Element	Schedule d COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element																											
.....																															

Sl. No.	Clause No.	Existing Provisions				New / Revised Clause					
		1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 months			1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 months		
		2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)		100%	Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.	2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)		100%	Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.
		3.	1x240 MVar Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla-II 765kV D/c line (2nd)				3.	1x240 MVar Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II			

Sl. No.	Clause No.	Existing Provisions	New / Revised Clause																												
		<p>The payment of Transmission Charges for any Element irrespective of its successful commissioning on or before its Scheduled COD shall only be considered after successful commissioning of the Element(s) which are pre-required for declaring the commercial operation of such Element as mentioned in the above table.</p> <p>Scheduled COD for overall Project: 18 months from Effective Date.</p>	<table border="1" data-bbox="1182 207 2020 289"> <tr> <td data-bbox="1182 207 1281 289"></td> <td data-bbox="1281 207 1465 289">765kV D/c line (2nd)</td> <td data-bbox="1465 207 1612 289"></td> <td data-bbox="1612 207 1822 289"></td> <td data-bbox="1822 207 2020 289"></td> </tr> </table> <p>The payment of Transmission Charges for any Element irrespective of its successful commissioning on or before its Scheduled COD shall only be considered after successful commissioning of the Element(s) which are pre-required for declaring the commercial operation of such Element as mentioned in the above table.</p> <p>Scheduled COD for overall Project: 18 months from Effective Date.</p>						765kV D/c line (2nd)																						
	765kV D/c line (2nd)																														
3.	Point No. 8 of Annexure 8 of RFP	<table border="1" data-bbox="321 597 1161 1416"> <thead> <tr> <th data-bbox="321 597 420 954">Sr. No</th> <th data-bbox="420 597 604 954">Name of the Transmission Element</th> <th data-bbox="604 597 751 954">Scheduled COD in months from Effective Date</th> <th data-bbox="751 597 961 954">Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project</th> <th data-bbox="961 597 1161 954">Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element</th> </tr> </thead> <tbody> <tr> <td data-bbox="321 954 420 1182">1.</td> <td data-bbox="420 954 604 1182">Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)</td> <td data-bbox="604 954 751 1182">18 months</td> <td data-bbox="751 954 961 1182">100%</td> <td data-bbox="961 954 1161 1416" rowspan="2">Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.</td> </tr> <tr> <td data-bbox="321 1182 420 1416">2.</td> <td data-bbox="420 1182 604 1416">2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II</td> <td data-bbox="604 1182 751 1416"></td> <td data-bbox="751 1182 961 1416"></td> </tr> </tbody> </table>	Sr. No	Name of the Transmission Element	Scheduled COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element	1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 months	100%	Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.	2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II			<table border="1" data-bbox="1182 597 2020 1416"> <thead> <tr> <th data-bbox="1182 597 1281 954">Sr. No</th> <th data-bbox="1281 597 1465 954">Name of the Transmission Element</th> <th data-bbox="1465 597 1612 954">Scheduled COD in months from Effective Date</th> <th data-bbox="1612 597 1822 954">Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project</th> <th data-bbox="1822 597 2020 954">Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element</th> </tr> </thead> <tbody> <tr> <td data-bbox="1182 954 1281 1182">1.</td> <td data-bbox="1281 954 1465 1182">Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)</td> <td data-bbox="1465 954 1612 1182">18 months</td> <td data-bbox="1612 954 1822 1182">100%</td> <td data-bbox="1822 954 2020 1416" rowspan="2">Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.</td> </tr> <tr> <td data-bbox="1182 1182 1281 1416">2.</td> <td data-bbox="1281 1182 1465 1416">2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II</td> <td data-bbox="1465 1182 1612 1416"></td> <td data-bbox="1612 1182 1822 1416"></td> </tr> </tbody> </table>	Sr. No	Name of the Transmission Element	Scheduled COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element	1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 months	100%	Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.	2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II		
Sr. No	Name of the Transmission Element	Scheduled COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element																											
1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 months	100%	Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.																											
2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II																														
Sr. No	Name of the Transmission Element	Scheduled COD in months from Effective Date	Percentage of Quoted Transmission Charges recoverable on Scheduled COD of the Element of the Project	Element(s) which are pre-required for declaring the commercial operation (COD) of the respective Element																											
1.	Fatehgarh-II PS – Bhadla-II PS 765kV D/c line (2nd)	18 months	100%	Elements marked at Sl. No. 1 to 3 are required to be commissioned simultaneously as their utilization is dependent on commissioning of each other.																											
2.	2 no. of 765 kV line bays each at Fatehgarh-II and Bhadla-II																														

Sl. No.	Clause No.	Existing Provisions				New / Revised Clause					
			for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)					for Fatehgarh-II PS – Bhadla- II PS 765kV D/c line (2nd)			
		3.	1x240 MVA Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd)				3.	1x240 MVA Switchable line reactor for each circuit at each end of Fatehgarh-II – Bhadla- II 765kV D/c line (2nd)			
		<p>We agree that the payment of Transmission Charges for any Element irrespective of its successful commissioning on or before its Scheduled COD shall only be considered after the successful commissioning of Element(s) which are pre - required for declaring the commercial operation of such Element as mentioned in the above table.</p> <p>Scheduled COD for the Project: 18 months from the Effective Date</p>					<p>We agree that the payment of Transmission Charges for any Element irrespective of its successful commissioning on or before its Scheduled COD shall only be considered after the successful commissioning of Element(s) which are pre - required for declaring the commercial operation of such Element as mentioned in the above table.</p> <p>Scheduled COD for the Project: 18 months from the Effective Date</p>				
4.	Specification for	Pile foundation shall be used for towers located in the river bed, or on river banks or in areas where river flow or river course is					Pile type foundation shall be used for towers located in river or creek bed or on bank of river having scourable				

Sl. No.	Clause No.	Existing Provisions	New / Revised Clause																																
	Transmission Line	anticipated to change based on previous years' hydrology data.	strata or in areas where river flow or change in river course is anticipated, based on detailed soil investigation and previous years' maximum flood discharge of the river, maximum velocity of water, highest flood level, scour depth & anticipated change in course of river based on river morphology data of at least past 20 years to ensure availability and reliability of the transmission line.																																
5.	Specific technical requirements for Substation	<p>2.1 765/√3 kV Single Phase Shunt Reactor</p> <p>.....</p> <table border="1"> <thead> <tr> <th>Sl. No.</th> <th>Description</th> <th>Unit</th> <th>Technical Parameters</th> </tr> </thead> <tbody> <tr> <td>24 v</td> <td>Minimum creepage distance</td> <td></td> <td>(Specific Creepage Distance: of 25mm/kV corresponding to highest line to line voltage)</td> </tr> <tr> <td></td> <td>Line bushing</td> <td>mm</td> <td>20000</td> </tr> <tr> <td></td> <td>Neutral bushing</td> <td>mm</td> <td>3625</td> </tr> </tbody> </table> <p>.....</p>	Sl. No.	Description	Unit	Technical Parameters	24 v	Minimum creepage distance		(Specific Creepage Distance: of 25mm/kV corresponding to highest line to line voltage)		Line bushing	mm	20000		Neutral bushing	mm	3625	<p>2.1 765/√3 kV Single Phase Shunt Reactor</p> <p>.....</p> <table border="1"> <thead> <tr> <th>Sl. No.</th> <th>Description</th> <th>Unit</th> <th>Technical Parameters</th> </tr> </thead> <tbody> <tr> <td>24 v</td> <td>Minimum creepage distance</td> <td></td> <td>(Specific Creepage Distance: of 31mm/kV corresponding to highest line to line voltage)</td> </tr> <tr> <td></td> <td>Line bushing</td> <td>mm</td> <td>24800</td> </tr> <tr> <td></td> <td>Neutral bushing</td> <td>mm</td> <td>4495</td> </tr> </tbody> </table> <p>.....</p>	Sl. No.	Description	Unit	Technical Parameters	24 v	Minimum creepage distance		(Specific Creepage Distance: of 31mm/kV corresponding to highest line to line voltage)		Line bushing	mm	24800		Neutral bushing	mm	4495
Sl. No.	Description	Unit	Technical Parameters																																
24 v	Minimum creepage distance		(Specific Creepage Distance: of 25mm/kV corresponding to highest line to line voltage)																																
	Line bushing	mm	20000																																
	Neutral bushing	mm	3625																																
Sl. No.	Description	Unit	Technical Parameters																																
24 v	Minimum creepage distance		(Specific Creepage Distance: of 31mm/kV corresponding to highest line to line voltage)																																
	Line bushing	mm	24800																																
	Neutral bushing	mm	4495																																
6.	Contents Table of TSA	Schedule: 9 Appendix III to V of Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2014	Schedule: 9 Appendix II & III of Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2019																																
7.	Article: 1 of TSA Definition	"Availability" in relation to the Project or in relation to any Element of the Project, for a given period shall mean the time in hours during that period the Project is capable to transmit electricity at its Rated Voltage and shall be expressed in percentage of total hours in the given period and shall be calculated as per the procedure contained in Appendix –III to Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2014 attached herewith in Schedule 9;	"Availability" in relation to the Project or in relation to any Element of the Project, for a given period shall mean the time in hours during that period the Project is capable to transmit electricity at its Rated Voltage and shall be expressed in percentage of total hours in the given period and shall be calculated as per the procedure contained in Appendix –II to Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2019 attached herewith in Schedule 9;																																
8.	Article:	8.1	8.1																																

Sl. No.	Clause No.	Existing Provisions	New / Revised Clause
	8 of TSA Availability	Calculation of Availability for the Elements and for the Project, as the case may be, shall be as per <u>Appendix III of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2014</u> , as applicable seven (7) days prior to the Bid Deadline and as appended in Schedule 9	Calculation of Availability for the Elements and for the Project, as the case may be, shall be as per <u>Appendix –II of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2019</u> , as applicable seven (7) days prior to the Bid Deadline and as appended in Schedule 9
9.	Article: 11 of TSA Force Majeure	11.7 Available Relief for a Force Majeure Event a..... b..... c. For the avoidance of doubt, it is clarified that the computation of Availability of the Element(s) under outage due to Force Majeure Event, as per Article 11.3 affecting the TSP shall be as per <u>Appendix III to the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2014</u> , as on seven (7) days prior to the Bid Deadline. For the event(s) for which the Element(s) is/are deemed to be available as per <u>Appendix III to the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2014</u> , then only the Non Escalable Transmission Charges, as applicable to such Element(s) in the relevant Contract Year, shall be paid by the Long Term Transmission Customers as per Schedule 5, for the duration of such event(s).	11.7 Available Relief for a Force Majeure Event a..... b..... c. For the avoidance of doubt, it is clarified that the computation of Availability of the Element(s) under outage due to Force Majeure Event, as per Article 11.3 affecting the TSP shall be as per <u>Appendix II to the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2019</u> , as on seven (7) days prior to the Bid Deadline. For the event(s) for which the Element(s) is/are deemed to be available as per <u>Appendix II to the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2019</u> , then only the Non Escalable Transmission Charges, as applicable to such Element(s) in the relevant Contract Year, shall be paid by the Long Term Transmission Customers as per Schedule 5, for the duration of such event(s).
10.	Schedule:5 of TSA Computation of Transmission Charges	1.1 g) The Availability shall be calculated as per the procedure specified in <u>Appendix III of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2014</u> as notified by CERC and as attached herewith.	1.1 g) The Availability shall be calculated as per the procedure specified in <u>Appendix II of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2019</u> as notified by CERC and as attached herewith.
11.	Schedule:9 of TSA	Appendix III of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations, 2014	<u>Appendix II of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2019 as Attached at Annex-A herewith.</u>

Appendix II of the Central Electricity Regulatory Commission (Terms and Conditions of Tariff) Regulations 2019

Procedure for Calculation of Transmission System Availability Factor for a Month

1. Transmission system availability factor for nth calendar month ("TAFPn") shall be calculated by the respective transmission licensee, got verified by the concerned Regional Load Dispatch Centre (RLDC) and certified by the Member-Secretary, Regional Power Committee of the region concerned, separately for each AC and HVDC transmission system and grouped according to sharing of transmission charges. In case of AC system, transmission System Availability shall be calculated separately for each Regional Transmission System and inter-regional transmission system. In case of HVDC system, transmission System Availability shall be calculated on consolidate basis for all inter-state HVDC system.
2. Transmission system availability factor for nth calendar month ("TAFPn") shall be calculated by consider following:
 - i) **AC transmission lines:** Each circuit of AC transmission line shall be considered as one element;
 - ii) **Inter-Connecting Transformers (ICTs):** Each ICT bank (three single phase transformer together) shall form one element;
 - iii) **Static VAR Compensator (SVC):** SVC along with SVC transformer shall form one element;
 - iv) **Bus Reactors or Switchable line reactors:** Each Bus Reactors or Switchable line reactors shall be considered as one element;
 - v) **HVDC Bi-pole links:** Each pole of HVDC link along with associated equipment at both ends shall be considered as one element;
 - vi) **HVDC back-to-back station:** Each block of HVDC back-to-back station shall be considered as one element. If associated AC line (necessary for transfer of inter- regional power through HVDC back-to-back station) is not available, the HVDC back-to-back station block shall also be considered as unavailable;
 - vii) **Static Synchronous Compensation ("STATCOM"):** Each STATCOM shall be considered as separate element.
3. The Availability of AC and HVDC portion of Transmission system shall be calculated by considering each category of transmission elements as under:

TAFMn (in %) for AC system:

$$= \frac{o \times AV_o + (p \times AV_p) + (q \times AV_q) + (r \times AV_r) + (u \times AV_u)}{(o + p + q + r + u)} \times 100$$

Where,

- o = Total number of AC lines.
- AV_o = Availability of o number of AC lines.
- p = Total number of bus reactors/switchable line reactors
- AV_p = Availability of p number of bus reactors/switchable line reactors
- q = Total number of ICTs.
- AV_q = Availability of q number of ICTs.
- r = Total number of SVCs.
- AV_r = Availability of r number of SVCs
- u = Total number of STATCOM.
- AV_u = Availability of u number of STATCOMs

TAFMn (in %) for HVDC System:

$$= \frac{\sum_{x=1}^s C_{xpb}(\text{act}) \times AV_{xpb} + \sum_{y=1}^t C_{ybtb}(\text{act}) \times AV_{ybtb}}{\sum_{x=1}^s C_{xpb} + \sum_{y=1}^t C_{ybtb}} \times 100$$

Where

- C_{xpb}(act) = Total actual operated capacity of xth HVDC pole
- C_{xpb} = Total rated capacity of xth HVDC pole

AV_{xpb}	=	Availability of x^{th} HVDC pole
$Cy_{btb}(\text{act})$	=	Total actual operated capacity of y^{th} HVDC back-to-back station block
Cy_{btb}	=	Total rated capacity of y^{th} HVDC back-to-back station block
AV_{ybtb}	=	Availability of y^{th} HVDC back-to-back station block
s	=	Total no of HVDC poles
t	=	Total no of HVDC Back to Back blocks

3. The availability for each category of transmission elements shall be calculated based on the weightage factor, total hours under consideration and non-available hours for each element of that category. The formulae for calculation of Availability of each category of the transmission elements are as per **Appendix-III**. The weightage factor for each category of transmission elements shall be considered as under:

- (a) For each circuit of AC line – Number of sub-conductors in the line multiplied by ckt-km;
- (b) For each HVDC pole- The rated MW capacity x ckt-km;
- (c) For each ICT bank – The rated MVA capacity;
- (d) For SVC- The rated MVAR capacity (inductive and capacitive);
- (e) For Bus Reactor/switchable line reactors – The rated MVAR capacity;
- (f) For HVDC back-to-back station connecting two Regional grids- Rated MW capacity of each block; and
- (g) For STATCOM – Total rated MVAR Capacity.

4. The transmission elements under outage due to following reasons shall be deemed to be available:

- i. Shut down availed for maintenance of another transmission scheme or construction of new element or renovation/upgradation/additional capitalization in existing system approved by the Commission. If the other transmission scheme belongs to the transmission licensee, the Member Secretary, RPC may restrict the deemed availability period to that considered reasonable by him for the work involved. In case of dispute regarding deemed availability, the matter may be referred to Chairperson, CEA within 30 days.
- ii. Switching off of a transmission line to restrict over voltage and manual tripping of switched reactors as per the directions of concerned RLDC.

5. For the following contingencies, outage period of transmission elements, as certified by the Member Secretary, RPC, shall be excluded from the total time of the element under period of consideration for the following contingencies:

- i) Outage of elements due to acts of God and force majeure events beyond the control of the transmission licensee. However, whether the same outage is due to force majeure (not design failure) will be verified by the Member Secretary, RPC. A reasonable restoration time for the element shall be considered by Member Secretary, RPC and any additional time taken by the transmission licensee for restoration of the element beyond the reasonable time shall be treated as outage time attributable to the transmission licensee. Member Secretary, RPC may consult the transmission licensee or any expert for estimation of reasonable restoration time. Circuits restored through ERS (Emergency Restoration System) shall be considered as available;
- ii) Outage caused by grid incident/disturbance not attributable to the transmission licensee, e.g. faults in substation or bays owned by other agency causing outage of the transmission licensee's elements, and tripping of lines, ICTs, HVDC, etc. due to grid disturbance. However, if the element is not restored on receipt of direction from RLDC while normalizing the system following grid incident/disturbance within reasonable time, the element will be considered not available for the period of outage after issuance of RLDC's direction for restoration;

Provided that in case of any disagreement with the transmission licensee regarding reason for outage, same may be referred to Chairperson, CEA within 30 days. The above need to be resolved within two months:

Provided further that where there is a difficulty or delay beyond sixty days, from the incidence in finalizing the recommendation, the Member Secretary of concerned RPC shall allow the outage hours on provisional basis till the final view.

6. Time frame for certification of transmission system availability: (1) Following schedule shall be followed for certification of availability by Member Secretary of concerned RPC:

- Submission of outage data by Transmission Licensees to RLDC/ constituents
 - By 5th of the following month;
- Review of the outage data by RLDC / constituents and forward the same to respective RPC – by 20th of the month;
- Issue of availability certificate by respective RPC – by 3rd of the next month.

Appendix-III

FORMULAE FOR CALCULATION OF AVAILABILITY OF EACH CATEGORY OF TRANSMISSION ELEMENTS

For AC transmission system

$$AV_o(\text{Availability of } o \text{ no. of AC lines}) = \frac{\sum_{i=1}^o W_i(T_i - T_{NAi})/T_i}{\sum_{i=1}^o W_i}$$

$$AV_q(\text{Availability of } q \text{ no. of ICTs}) = \frac{\sum_{k=1}^q W_k(T_k - T_{NAk})/T_k}{\sum_{k=1}^q W_k}$$

$$AV_r(\text{Availability of } r \text{ no. of SVCs}) = \frac{\sum_{l=1}^r W_l(T_l - T_{NAL})/T_l}{\sum_{l=1}^r W_l}$$

$$AV_p(\text{Availability of } p \text{ no. of Switched Bus reactors}) = \frac{\sum_{m=1}^p W_m(T_m - T_{NA_m})/T_m}{\sum_{m=1}^p W_m}$$

$$AV_u(\text{Availability of } u \text{ no. of STATCOMs}) = \frac{\sum_{n=1}^u W_n(T_n - T_{NAn})/T_n}{\sum_{n=1}^u W_n}$$

$$AV_{x_{bp}}(\text{Availability of an individual HVDC pole}) = \frac{(T_x - T_{N_x})}{T_x}$$

$$AV_{y_{btb}}(\text{Availability of an individual HVDC Back-to-back Blocks}) = \frac{(T_y - T_{NAy})}{T_y}$$

For HVDC transmission system

For the new HVDC commissioned but not completed twelve months;

For first 12 months: $[(AV_{x_{bp}} \text{ or } AV_{y_{btb}}) \times 95\% / 85\%]$, subject to ceiling of 95%.

Where,

- o = Total number of AC lines;
- AV_o = Availability of o number of AC lines;
- p = Total number of bus reactors/switchable line reactors;
- AV_p = Availability of p number of bus reactors/switchable line reactors;
- q = Total number of ICTs;
- AV_q = Availability of q number of ICTs;
- r = Total number of SVCs;
- AV_r = Availability of r number of SVCs;
- U = Total number of STATCOM;

AV_u	=	Availability of u number of STATCOMs;
W_i	=	Weightage factor for i th transmission line;
W_k	=	Weightage factor for k th ICT;
W_l	=	Weightage factors for inductive & capacitive operation of l th SVC;
W_m	=	Weightage factor for m th bus reactor;
W_n	=	Weightage factor for n th STATCOM.
$T_i, T_k, T_l, T_m, T_n, T_x, T_y$	-	The total hours of i th AC line, k th ICT, l th SVC, m th Switched Bus Reactor & n th STATCOM, x th HVDC pole, y th HVDC back-to-back blocks during the period under consideration (excluding time period for outages not attributable to transmission licensee for reasons given in Para 5 of the procedure)
$T_{NAi}, T_{NAk}, T_{NAL}, T_{NAM}, T_{NAN}, T_{NAX}, T_{NAY}$	-	The non-availability hours (excluding the time period for outages not attributable to transmission licensee taken as deemed availability as per Para 5 of the procedure) for i th AC line, k th ICT, l th SVC, m th Switched Bus Reactor, n th STATCOM, x th HVDC pole and y th HVDC back-to-back block .